

Schedule of Requirements

NAME OF THE PROCURING ENTITY : **MUNICIPALITY OF SUMILAO, BUKIDNON**
PROJECT TITLE : **REBIDDING FOR THE PROCUREMENT OF
VARIOUS CONSTRUCTION MATERIALS FOR
DIFFERENT PROJECTS IN BARANGAY OF SUMILAO**
REFERENCE NUMBER : **12980547**

The delivery schedule is expressed as weeks/month stipulated share after a delivery date which is the date of delivery to the project site.

Item No.	Specification/s	Qty	Unit	Delivered Weeks/Months
1	4thk Concrete Hollow Block	2205	pcs	15 days
2	Screen sand	44	cu.m	15 days
3	Portland cement	430	bags	15 days
4	Fine sand	8.5	cu.m	15 days
5	12mm def. bars	162	pcs	15 days
6	10mm def. bars	183	pcs	15 days
7	No. 16 Tie Wire	17	kg	15 days
8	20 pcs. 2x2x8 coco lumber	53.33	bd.ft	15 days
9	20 pcs. 2x3x8 coco lumber	80	bd.ft	15 days
10	1/4 thk marine plywood	1	sheet	15 days
11	4" long common wire nails	4	kg	15 days
12	2 1/2 common wire nails	2	kg	15 days
13	1" long common wire nails	0.5	kg	15 days
14	2x4 Rectangular Tube (rafter & girt)	7	pcs	15 days
15	3"C-purlins	50	pcs	15 days
16	2x3 Rectangular Tube (chimney Exhaust)	1	pc	15 days
17	1/8 thk X1 Flat Bars (Fascia Frame)	11	pcs	15 days
18	1/8 thk X1 Flat Bars (Fascia Frame Member)	3	pcs	15 days
19	4"0 Gi pipe sch40(post) Cutting Disc (metal)	2	pcs	15 days
20	12mm0 plain round bars	7	pcs	15 days
21	Fuji welding rod #12	25	kg	15 days
22	4"0 Cutting disc (Metal)	47	pcs	15 days
23	Enamel paint (black)	2	gal	15 days
24	1 paint brush	2	pcs	15 days

25	Paint thinner	1	gal	15 days
26	1.04 width Pre-painted, Roofing (Baguio green)	81.34	lm	15 days
27	25 width, Pre-painted Fascia Molding (white)	17	pcs	15 days
28	2 1/2 long Tec screw	1170	pcs	15 days
29	1/8"0 x 3/4 long blind rivets	2	box	15 days
30	Vulca Seal	1	can	15 days
31	1"x2 Rectangular Tube Frame	4	pcs	15 days
32	1/4 thk Hard Flex	4	sheet	15 days
33	0.60x0.60 ceramic Floor Tiles (unglazed)	185	pcs	15 days
34	Tile grout	3	kg	15 days
35	Tile cutter	1	pc	15 days
36	100pcs 2x2x12 coco lumber	283.33	bd.ft	15 days
37	10mm thk Marine Plywood	12	sheet	15 days
38	Assorted nails	7	kg	15 days
39	3/4 gravel	18	cu.m	15 days
40	2"x4 rectangular tube	22	pcs	15 days
41	3"0 G.I pipe sched. 40	2	pcs	15 days
42	1/2"0 G.I pipe sched.40	4	pcs	15 days
43	1/8 thick x1" Flat bar	4	pcs	15 days
44	1/8 thick x1"x1 angle bar	7	pcs	15 days
45	60pcs (0.40mmx1040mmx5.80m long Span Rib Type Roofing (color green)	46.40	lm	15 days
46	10 width x 2.4 length pre-painted fascia molding	9	pcs	15 days
47	1/8 Dia drill bit (metal)	2	pcs	15 days
48	2x2 square tube (for steel Gate & Railings) 1.5mm	11	pcs	15 days
49	1"x1 square tube (for Railings)	28	pcs	15 days
50	26pcs (0.40mmx1040mmx3.10mlong) span rib type roof. (green)	80.6	lm	15 days
51	1x2x2.0mm thick Rectangular Tube (for steel gate)	18	pcs	15 days
52	3" long cylindrical hinge	6	pcs	15 days
53	Fuji Welding rod (20kgs)	1	box/pack	15 days
54	Poxy primer	5	gal	15 days
55	Rubberized Floor paint	60	gal	15 days
56	Paint reducer	17	gal	15 days

57	Paint Brush 1"	4	pcs	15 days
58	Paint Brush 2"	4	pcs	15 days
59	Paint Brush 9"	6	pcs	15 days
60	Skim coat	30	bags	15 days
61	Latex Paint semi-gloss	30	gal	15 days
62	Latex paint Flat wall	15	gal	15 days
63	Stick well (glue)	10	kg	15 days
64	Paint brush #4	12	pcs	15 days
65	Paint tray	4	pcs	15 days
66	Sandpaper (no.120)	3	pcs	15 days
67	Sandpaper (no.100)	3	pcs	15 days
68	Red oxide	20	gal	15 days
69	Black enamel paint (gloss)	25	gal	15 days
70	Paint thinner	10	gal	15 days
71	Baby paint roller	6	pcs	15 days
72	Paint roller 9	6	pcs	15 days

Submitted by: : **JHO ANN Q. CLEOPAS**
(Printed Name & Signature)

Designation : **Authorized Representative**

Name of Firm : **MIKATA PRIME CORPORATION**

Date : **May 19, 2026**